

FIRE RESISTANCE TEST REPORT

SUSPENDED CEILING SYSTEM

in accordance with **BS 476-22: 1987**

Test Sponsor: Kingtec Building Materials (HK & Macau) Limited
Unit 4, 3/F., Block B, Shatin Ind., Centre,
5-7 Yuen Shun Circuit, Shatin,
New Territories, Hong Kong.
Tel: 852-2640 8688 Fax: 852-2142 8128

Test Laboratory: Forte Testing and Consultants Company Limited
Contact Information:
Flat 31, 5/F., My Loft, 9 Hoi Wing Road,
Tuen Mun, Hong Kong.
Tel: 852-2152 0638 Fax: 852-3186 2737

Report Number: IT 16-127

Date of Issue: 2016-09-12

HKAS has accredited Forte Testing and Consultants Company Limited (Reg. No. 191 - TEST) under HOKLAS for specific laboratory activities as listed in the HOKLAS directory of accredited laboratories. The results shown in this report were determined by this laboratory in accordance with terms of accreditation. This report may not be reproduced, except in full, without prior written approval from FORTE.

HOKLAS Approved Signatory:


CHENG San Mei, Sammi

1. Scope of Test

This report is a record of a fire resistance test conducted by Forte Testing and Consultants Co., Ltd. in conformity with requirements in BS 476-20: 1987 "Method for determination of the fire resistance of elements of construction (general principals)" and with the particular requirements in Clause 9; BS 476-22: 1987 "Methods for determination of the fire resistance of non-loadbearing elements of construction".

A specimen of Kingtec Hawk Pan suspended ceiling system was overall sized 4020 mm (width) x 3030 mm (long) was constructed with steel channel supporting grid. A layer of 9 mm (thick) Kingtec Hawk Pan board was fastened to the underside of the steel channel grid members with rock wool laid out on the top of the board layer. The specimen was supplied for test by Kingtec Building Materials (HK & Macau) Limited, the Sponsor.

The specimen achieved the following fire resistance:

INTEGRITY	65 Minutes
INSULATION	63 Minutes

2. Test Information


Test Laboratory:	FORTE Testing and Consultants Company Limited	
Test Location:	State Key Laboratory of Subtropical Building Science, North Campus of South China University of Technology, 381 Wushan Road, Tianhe District, Guangzhou Province, China.	
Test Sponsor:	Kingtec Building Materials (HK & Macau) Limited	
Fire Board Manufacturer:	Yichun Kingtec Building Materials Industrial Company Limited	
ID no. of the Specimen:	QT16-185	
Date Received:	2016-07-18	
Test Number:	QT16-185	
Date Tested:	2016-07-21	Start Time: 15:15
Approved Test Operator from FORTE:	Mr. Walter Tang	
Witness of the Test:	Mr. Liu Hai Hui and Ms. Lilian Tse – Official Delegates of the Sponsor	
Report Issue Record:	Version 1 – 2016-09-12	

6.2 Unexposed Surface Temperature Rise – Fixed Surface Thermocouples

The temperature rises of unexposed surface of the specimen measured by fixed surface thermocouples over the test period were shown in Figure 4.

The average temperature rise measured at 63.4 minute of test was 140.8°C, which was in excess of 140°C limit; whereas the maximum temperature rise measured at 63.4 minute of test was 180.4°C at U2, which was in excess of 180°C limit.


Figure 4. Average and maximum unexposed surface temperature rises of the specimen over the test period.



6.3 Ambient Temperature

The ambient temperature over the test period was recorded and shown in Figure 5. The ambient temperature at the commencement of test was 34.7°C.

Figure 5. Ambient temperature over the test period.



6.4 Pressure

The pressure inside furnace at 800 mm underside the horizontal test construction was maintained to be 10 ± 2 Pa over the test period after 5 minutes from commencement of the test.

6.5 Lateral Deflections

Measured lateral deflections over the test period are summarized in the following table. A positive measurement indicates a movement towards into the furnace and vice versa.

Measurements were taken in mm.

Maximum deflection value of the specimen is BOLDDED in the following table.

Positions \ Time (min)	0	10	20	30	40	50	60	65
D1	0.0	+3	+5	+6	+7	+7	+7	+8
D2	0.0	+8	+11	+14	+15	+17	+18	+18
D3	0.0	+4	+6	+6	+7	+7	+7	+7

